

SECTION 024119 - SELECTIVE DEMOLITION

1.1 FIELD CONDITIONS

- A. Owner will occupy portions of building adjacent to selective demolition area.
- B. Hazardous Materials: Removed by Contractor prior to start of the Work.

1.2 WARRANTY

- A. Existing Warranties: Not applicable.

1.3 EXAMINATION

- A. Perform an engineering survey of condition of building.

1.4 PREPARATION

- A. Refrigerant: Remove according to 40 CFR 82.

1.5 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Utility Shut Off: Coordinated with Owner and provided by Contractor.

1.6 DISPOSAL OF DEMOLISHED MATERIALS

- A. Dispose of in an EPA-approved landfill.

1.7 SELECTIVE DEMOLITION SCHEDULE

- A. Existing generator unit will be removed and relocated by Owner. Associated control panels shall be removed and salvaged. Return all components to owner.
- B. Contractor will remove existing concrete pad and foundation system.
- C. Contractor will disconnect existing gas piping at service point.

END OF SECTION 024119